



DAV PUBLIC SCHOOL, MALIGHAT MUZAFFARPUR (BIHAR)

E-mail– prinmalighat@gmail.com

Website: www.davpsmalighat.com

Contact No. 9263182202, 0621-2283776

TENDER NOTICE

Tender No.: DAV/MGT/2025-26/02

Date: 17/12/2025

01.	Name of work	Construction of Stage at DAV Public School, Malighat, Muzaffarpur,
02.	Total Length	40'-0" x 32'-0" + 2 x 3'-0" x 8'-10" = 1332.98 Sq. ft.
03.	Date of Tender Notification	17/12/2025
04.	Last Date/Time for Receipt of Bids	Offline Mode:24-12-2025upto05:00PM Online Mode:25-12-2025upto04:00PM
05.	Name & Address of inviting Tender	DAV Public School, Malighat, Near BMP-06, Muzaffarpur,
06.	Time of Completion	Within 30 Days from the date of work order

Interested parties may submit their sealed quotations, along with requisite credentials, to the undersigned on or before 24.12.2025 by 05:00 PM.

Quotations may also be submitted on line to [prinmalighat@gmail.com] on or before 25.12.2025 by 04:00 PM.

The School's Building Sub-Committee reserves the right to accept or reject any or all quotations without assigning any reason thereof.

TERMS & CONDITIONS

- ❖ Only quality materials of reputed brands and standard workmanship will be accepted.
- ❖ The interested firm must submit two separate sealed quotations—one Technical and one Financial.
- ❖ The school shall not be liable to pay any tax, freight, or other charges not explicitly mentioned in the quotation at the time of acceptance. TDS will be deducted as per Income Tax rules.
- ❖ Upon acceptance, the quotation shall be treated as a binding contract, and the contractor must comply with all applicable Government of India and Government of Bihar norms.
- ❖ The quantities indicated may be increased or decreased at the discretion of the undersigned without assigning any reason.
- ❖ Acceptance of work and materials shall be subject to inspection by the undersigned/architect and may be rejected if not in conformity with approved samples or specifications.


- ❖ The quoted rates shall remain valid till completion of the construction. No revision shall be permitted.
- ❖ Payment shall be made through A/c Payee cheque, as per the agreement and duly approved by the architect, in accordance with DAV CMC norms.
- ❖ Quotations not complying with the above conditions shall be liable for rejection.
- ❖ The site and proposed drawings are open for inspection prior to bidding.
- ❖ Compliance with all labour safety and security norms prescribed by the Government shall be the sole responsibility of the selected firm.
- ❖ Waste management and disposal shall be the responsibility of the selected firm, at its own cost.
- ❖ The decision of the School Building Sub-Committee shall be final and binding in all matters.

MEMBER OF BUILDING SUB- COMMITTEE

1. Dr. K.C. Satapathy, Chairman, DAV PS, Malighat, Muzaffarpur, Bihar.
2. Shri S.K. Jha, Manager, DAV PS, Malighat, Muzaffarpur, Bihar.
3. Shri A.C. Jha, ARO, DAV PS, Malighat, Muzaffarpur, Bihar.
4. Dr. Himanshu Kumar Pandey, Principal, DAV PS, Malighat, Muzaffarpur, Bihar.
5. Mr. R.C. Sharma, Principal, DAV PS, Bakhari, Darbhanga Road, Muzaffarpur.
6. Mr. Murai Pathak, Headmaster, DAV PS, Narhan, East Champaran.
7. Mr. B.K. Singh, Civil Engineer.
8. Senior Teacher, DAV PS, Malighat, Muzaffarpur, Bihar.


 (Dr. Himanshu Kumar Pandey)
 Principal

Principal
 D.A.V. Public School
 Malighat, Muzaffarpur


 (Shri S. K. Jha)
 Manager

Manager
 D.A.V. Public School
 Malighat, Muzaffarpur

(Issued with the approval of the competent authority and in accordance with DAV CMC guidelines.)

Sl. No.	S.O.R.	DESCRIPTION	Unit	Qty.	Rate	Amount
		(1) OPEN STAGE				
		Open stage Area = 40'-0" x 32'-0" + 2 x 3'-0" x 8'-10" = 1332.98 Sq.ft.				
		SECTION-I (EARTHWORK/SAND FILLING)				
1	20.3A.1	Making 25cm (10") dia bore upto 4 mtr. depth below ground with hand auger of approved quality in ordinary soil (vide classification of soil item A) true to plumb and without eccentricity in any stage of operation and disposal of the excavated earth upto 50 mtr. lead including all lifts all complete as per approved design and direction of E/I.	Rm	40.55		
2	2.8	Earth work in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.				
	2.8.1	All kinds of soil.	Cum	2.28		
3	2.28	Supplying and filling in plinth with local sand under floors including watering, ramming, consolidating and dressing complete.	Cum	90.17		
		SECTION-II (R.C.C./P.C.C. WORK)				
4	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level.				
	4.1.3	1:2:4 (1 cement, 2 coarse sand, 4 graded stone aggregate 20mm nominal size.)	Cum	9.61		
5	5.1	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work up to plinth level.				
	5.1.2	1:1.5:3 (1 Cement, 1.5 coarse sand, 3 graded stone aggregate 20mm nominal size.)	Cum	6.60		
6	5.9	Centring and shuttering including strutting, propping etc. and removal of form for:				
	5.9.5	Lintels, beams, plinth beams, girders, breast summer and cantilevers.	Sqm	29.00		
	5.9.6	Columns, pillars, piers, abutments, posts and struts.	Sqm	9.11		
7	5.22	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete:				
	5.22.1	Mild steel 6.0mm dia.	Kg	85		

Sl. No.	S.O.R.	DESCRIPTION	Unit	Qty.	Rate	Amount
7	5.22.7B	Thermo-Mechanically treated bars TMT C-500 - 10mm dia.	Kg	155		
	5.22.7A	Thermo-Mechanically treated bars TMT C-500 - 8mm dia.	Kg	172		
	5.22.7C	Thermo-Mechanically treated bars TMT C-500 - 12mm dia.	Kg	120		
		SECTION-III (MASONRY WORK)				
8	6.1A	Brick work with bricks of class designation 100A in foundation and plinth in				
	6.1.14A	Cement mortar 1:6 (1 cement, 6 coarse sand).	Cum	6.34		
		SECTION-IV (FLOORING WORK)				
9	11.23	Marble stone flooring with 18mm thick marble stone (Sample of marble shall be approved by engineer-in-charge) over 20mm (average) thick base of C.M. 1:4 (1 Cement: 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing complete with:				
	11.23.2	Rajnagar plain white marble 18mm thick above 0.10 Sqm. upto 0.20 Sqm.	Sqm	123.88		
10	11.22	Tile work in skirting risers of steps and dado (upto 2m height) over 12mm thick bed of cement mortar 1:3 (1 Cement: 3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm including pointing in white cement mixed with pigment of matching shade complete:				
	11.22.1	Marble tile (polished) Rajnagar 8mm thick.	Sqm	2.23		
11	11.36	Providing and laying first quality ceramic glazed wall tiles confirming to IS 15622 (Thickness to be specified by manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by engineer in charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement, 3 coarse sand) and jointed with grey cement slurry @ 3.3 Kg/sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	38.66		
12	11.72	Providing designation 100A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty, all complete as per building specification and direction of E/I.	Sqm	124.44		

		SECTION-V (PLASTER WORK)				
Sl. No.	S.O.R.	DESCRIPTION	Unit	Qty.	Rate	Amount
13	13.11	12mm cement plaster of mix:				
	13.11.4	1:6 (1 cement; 6 coarse sand).	Sqm	38.66		
14	13.12	15mm cement plaster on rough side of single or half brick wall of mix:				
	13.12.4	1:6 (1 cement; 6 coarse sand).	Sqm	9.38		
		SECTION-VI (MISCELLANEOUS WORK)				
15	MR	Providing and fixing of 2" dia M.S. pipes sockets in floors.	No.	11		
		SECTION-VII (DISMANTLING WORK)				
16	MR	Dismantling of wall, cleaning and disposal of material etc. complete.	LS			
		SECTION-VIII (STEEL WORK)				
17	10.36	Providing and fixing stainless steel (Grade 304) stair, railing made of Hollow tubes, channels, plates etc. including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i.e. fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc. of required size, on the top of the floor or the side of waist slab with suitable arrangement as per the approval of Engineer-in-charge (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	Kg	7.25		
TOTAL						
ROUND UP						
Cost of construction per sq.ft.						